

Construction Method:
Horizontal Directional Drilling



Project: Camarillo Airport Water Improvement Project

Location: Camarillo, CA

Job Scope:

- ❖ Trenchless Feasibility Study
- ❖ HDD Alignment Study and Profile
- ❖ Pullback and Stress Calculations
- ❖ Geotechnical Risk Evaluation
- ❖ Cost Estimates
- ❖ Construction Schedules
- ❖ Specialized Construction Inspection



Project Description:

Staheli Trenchless Consultants designed and evaluated the construction feasibility of the installation of a 16-inch water main pipeline for the City of Camarillo. The upgrade included 1,900 feet of pipeline installed beneath an active runway and taxiway of the Camarillo Airport, precluding a continuous open-cut option for construction. After review of the geotechnical conditions and project constraints, STC designed a horizontal directional drill to install the new water main.

Challenges for the project design included construction scheduling associated with working beneath an active runway and taxiway, and a creative pullback layout requiring lofting above the County flood control channel just north of the airport. Magnetic interference associated with the active airport also led to challenges associated with drill navigation. STC provided full time specialized construction management and inspection during all stages of the HDD installation. This project was successfully completed in 2015.



**Staheli Trenchless
Consultants**
ph: 425-205-4930

www.stahelitrenchless.com